

	F.R. DIV. 6	TEXAS	BR 99 (99), ETC.	SHEET
	COUNTY		HWY	CONT 9999-99-99, ETC

GENERAL NOTES AND SPECIFICATION DATA--  
-----

GENERAL:  
-----

THE CONTRACTOR MAY USE PORTIONS OF THE RIGHT-OF-WAY TO STORE MATERIALS AND EQUIPMENT AND FOR PLANT SITES AND OTHER USES WITH THE APPROVAL OF THE ENGINEER. MATERIALS, EQUIPMENT, ETC., MUST EITHER BE LOCATED OUTSIDE THE 16 FEET TRAFFIC SAFETY CLEARANCE ZONE OR BE ADEQUATELY PROTECTED.

THE SLOPES INDICATED ON THE TYPICAL SECTIONS MAY BE VARIED WHEN FIXED FEATURES REQUIRE. THEY WILL BE RE-ESTABLISHED AS DIRECTED BY THE ENGINEER.

ANY WORK NECESSARY TO PROVIDE TEMPORARY INGRESS AND EGRESS DURING CONSTRUCTION (SUCH AS BUILDING GRAVEL RAMPS, ETC.) WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED AS SUBSIDIARY WORK TO THE VARIOUS BID ITEMS.

THE CONTRACTOR SHALL CONTACT (1-800-DIG-TESS) AT LEAST 48 HOURS PRIOR TO ANY WORK PERTAINING TO DIGGING OR ANY WORK TO BE DONE IN THE IMMEDIATE VICINTY OF A UTILITY LINE.

DUST CAUSED BY CONSTRUCTION OPERATIONS SHALL BE CONTROLLED BY APPLYING WATER IN CONFORMANCE WITH THE REQUIREMENTS OF ITEM 204, "SPRINKLING". SPRINKLING FOR DUST CONTROL WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED AS SUBSIDIARY WORK TO THE VARIOUS BID ITEMS.

THERE ARE NO "REFERENCE MARKERS" WITHIN THE PROJECT LIMITS.

THE FOLLOWING STANDARD DETAIL SHEETS HAVE BEEN MODIFIED:

CTBI (1)-99 (MOD)  
PCTB (3)-94 (MOD)

THE CONTRACTOR IS ADVISED THAT A 60 MPH CONSTRUCTION SPEED ZONE WILL BE APPLICABLE FOR THIS PROJECT. THE CONSTRUCTION SPEED ZONE SHALL BE LIMITED TO THE ACTUAL WORK AREAS UNDER CONSTRUCTION.

THE CONTRACTOR SHALL VERIFY ALL EXISTING GRADES, ELEVATIONS, AND CROSS SLOPES THAT WILL CONNECT TO ANY PROPOSED GRADES AND ELEVATIONS. IF ADJUSTMENTS ARE WARRANTED, THE CONTRACTOR SHALL SUBMIT PROPOSED CHANGES TO THE ENGINEER FOR VERIFICATION.

SPECIFICATION DATA  
-----

SHEET A  
-----

	F.R. DIV. 6	TEXAS	BR 99 (99), ETC.	SHEET
	COUNTY		HWY	CONT 9999-99-99, ETC

GENERAL NOTES AND SPECIFICATION DATA--  
-----

GENERAL:, CONT'D

CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL EXCESS MATERIAL FROM BRIDGE SUBSTRUCTURE RESULTING FROM ALL CONSTRUCTION INCLUDING PLANING, SEAL COAT AND ACP OVERLAYS. THIS WORK WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED SUBSIDIARY TO VARIOUS BID ITEMS IN THE CONTRACT.

ITEM 105:  
-----

ALL MATERIAL REMOVED UNDER ITEM 105 SHALL BECOME THE PROPERTY OF THE CONTRACTOR.

ITEM 110:  
-----

BEFORE GRADING IS BEGUN, THE VEGETATIVE COVER WITHIN THE AREAS TO BE GRADED SHALL BE BLADED INTO A WINDROW OUTSIDE THE LIMITS OF THE SLOPES. AFTER ALL GRADING IS COMPLETE, THE VEGETATIVE COVER SHALL BE SPREAD OVER THE ADJACENT DISTURBED AREAS. THIS WORK WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED AS SUBSIDIARY WORK TO THE VARIOUS BID ITEMS.

PRIOR TO CONTRACT LETTING, REPRODUCIBLE EARTHWORK CROSS-SECTIONS WILL BE AVAILABLE AT THE DISTRICT OFFICE. THEY MAY BE BORROWED BY COPYING SERVICE COMPANIES TO MAKE COPIES FOR PROSPECTIVE BIDDERS AT THE PROSPECTIVE BIDDER'S EXPENSE.

AFTER CONTRACT LETTING, ONE COPY OF THE EARTHWORK CROSS-SECTIONS WILL BE FURNISHED TO THE CONTRACTOR FREE OF CHARGE.

ITEM 164:  
-----

THE BUFFALO GRASS SEED SHALL BE TREATED FOR DORMANCY WITH POTASSIUM NITRATE.

ITEM 166:  
-----

SPECIFICATION DATA  
-----

SHEET B  
-----